



Highway Department

Jason Benson
County Engineer

Richard S. Sieg
Superintendent

Thomas B. Soucy, P.E.
Design and Construction
Engineer

August 24, 2011
ADDENDUM 1

To: All prospective bidders on Project FL1103 & CB1101, scheduled for the September 1, 2011 Bid Opening.

The following is a clarification of Bid Quantities:

COMMON EXCAVATION – TYPE A:

2606 CY is the in place quantity required to bring the existing road back to design grades. (See cross sections). Some of this material may be available on site from the adjacent project. Borrow will be required for the roadbed and may be required for the transition areas depending on suitable material available.

BORROW - EXCAVATION:

2500 CY is an estimated quantity that may be needed from a borrow source to bring the embankment to finished grades. The borrow site shall be approved for SHPO compliance. The pay quantity shall be an in place measurement at the borrow source.

Sincerely,



Jason Benson
County Engineer

1201 Main Avenue West
West Fargo, North Dakota
58078-1301

701-298-2370
Fax: 701-298-2395